



APPLICATION FOR SIDEWALK
MATCHING PROGRAM

Fee: \$3.50/Sq-ft

Date: _____

Name: _____

Mailing Address: _____

Phone: _____

Email: _____

I/We, _____ request to participate in the City's Sidewalk
(Print Name/s)

Matching Program. The sidewalks to be replaced are located at: _____
(Print address)

The length and width of sidewalk to be replaced is approximately: _____.

This program is for residential sidewalks only. Requests shall be referred to the Community Development Coordinator at the City of Macomb for review. If the request is approved, the City participation in the program will be \$3.50 per square foot and I will be responsible for all other costs incurred. In addition, I will be required to obtain a permit and either hire a private contractor to do work, or I may do the work myself. Upon completion, the sidewalk will be inspected by the City and must meet the City's required construction standards (see page two) before reimbursement will be made.

Requested By: _____
Signature

Signature

Approved/Denied By: _____
Signature of Public Official

Title

Date: _____


Comments:

PCC SIDEWALK NOTES:

1. PORTLAND CEMENT CONCRETE SIDEWALK SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 424 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE NOTES LISTED HERE.
2. IF CONSTRUCTED AS A REPLACEMENT FOR AN EXISTING SIDEWALK, EXISTING SIDEWALK SHALL BE SAWCUT FULL DEPTH PERPENDICULAR TO THE CENTERLINE PRIOR TO CONSTRUCTING NEW ADJACENT SIDEWALK.

PCC SIDEWALK SPECS

1. CONCRETE SHALL BE IDOT CLASS SI
2. AIR ENTRAINED - 5% TO 8%
3. MINIMUM COMPRESSIVE STRENGTH - 3500 PSI @ 14 DAYS
4. SLUMP - 2" TO 4"
5. APPROVED CURING METHOD PER ARTICLE 1022.01 (C)
6. TOOLED OR SAWED JOINTS AT 4'-0" MIN TO 6'-0" MAXIMUM CENTERS PERPENDICULAR TO THE CENTERLINE. JOINTS SHALL BE 1/4 THE DEPTH OF THE SLAB AND EDGED WITH 1/4" RADIUS TOOL. 1/2" EXPANSION JOINTS SHALL BE PLACE AT 100' MAX. SPACING PER ARTICLE 424.07 OF THE STANDARD SPECS..
7. PROVIDE A BRUSHED FINISH IN ACCORDANCE WITH ART. 424.06 OF THE STANDARD SPECIFICATIONS.
8. THE SIDEWALK SHALL BE THICKENED TO 6" WHEN THROUGH A RESIDENTIAL DRIVEWAY OR TO 7" THROUGH A COMMERCIAL DRIVEWAY. THE THICKENED SIDEWALK SHALL THEN TAPER FROM DRIVEWAY PAVEMENT DEPTH TO SIDEWALK DEPTH IN 6'.



TYPICAL SECTION

* SIDEWALKS CONSTRUCTED ADJACENT TO BACK OF CURB SHALL HAVE A MINIMUM WIDTH OF 6'-0"



CITY OF MACOMB, ILLINOIS
PUBLIC WORKS DEPARTMENT
233 CENTER STREET
MACOMB, ILLINOIS 61455
(309) 833-2821

STANDARD DETAILS

SIDEWALK DETAIL

DATE: 3-1-18

CHECKED: SC/MC

SHEET NO.

202